INCH - POUND

MIL-STD-1285R

2 Apr 1990

SUPERSEDING

MIL-STD-1285A 7 FEBRUARY 1972

### **MILITARY STANDARD**

# MARKING OF ELECTRICAL AND ELECTRONIC PARTS



AMSC N/A AREA 59GP

#### FOREWORD

- 1. This military standard is approved for use by all Departments and Agencies of the Department of Defense.
- 2. Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: U. S. Army Laboratory Command, Attn: SLCET-R-S, Fort Monmouth, NJ 07703-5000.
- 3. This military standard provides uniform marking requirements for electrical and electronic parts. The requirements that are common to all parts are contained in sections 4 and 5. Individual requirements applicable to specific parts are contained in the appendix FSC sections of this standard. These sections are numbered to identify the applicable federal supply class (such as FSC section 5905 Resistors).
- 4. The requirements of this standard need not be applied to existing acquisition documents, however, they should be considered for adoption whenever such documents are revised. It is not the intent to apply this standard to new detail specifications added to existing military specifications.

#### CONTENTS

| PARAGRAPH            |   | PAGE          |
|----------------------|---|---------------|
| 1.1                  | SCOPE   | 1             |
| 1.2                  | Applicability   | 1             |
| 2.                   | APPLICABLE DOCUMENTS  | 2             |
| 2.1.1                | Specifications, standards, and handbooks Other Government documents, drawings, and publications                     | 2             |
| 2.2                  | Non-Government publications   | 3             |
| 3.                   | DEFINITIONS   | 4             |
| 3.1<br>3.2<br>3.3    | Altered item drawing  | 4 4           |
| 3.4                  | Commercial, off-the-shelf (OTS) products (also referred to as commercial products)                                  | 4             |
| 3.5                  | Design activity   | 4             |
| 3.7<br>3.8<br>3.9    | Design activity, identification Design activity, original   | 4<br>4<br>4   |
| 3.10<br>3.11         | Document  | 4             |
| 3.12<br>3.13<br>3.14 | Manufacturer  | 4<br>4<br>4   |
| 3.15<br>3.16         | Order of precedence Part or Identifying Number (PIN) marking  | 5<br>5        |
| 3.17<br>3.18         | Physical characteristics marking Acquisition document   | 5<br>5        |
| 3.19<br>3.20<br>3.21 | Selected item drawing   | 5<br>5<br>5   |
| 3.22 3.23            | Source control drawing  | 5<br>5        |
| 3.24<br>3.25<br>3.26 | Specification control drawing   | 5<br>5<br>5   |
| 3.27                 | Warranty  | 5             |
| 4.<br>4.1            | GENERAL REQUIREMENTS  | <b>6</b><br>6 |
| 4.2<br>4.3<br>4.4    | Marking process   | 6<br>6        |
| 4.5<br>4.5.1         | Part identification marking Approved standards marking  | <b>6</b><br>6 |
| 4.5.2<br>4.5.3       | Approved government specification marking Marking parts acquired from, but not manufactured by, the design activity | 6             |
| 4.5.4<br>4.5.5       | Marking of altered or selected items Marking of source control items  | 7             |
| 4.5.6<br>4.5.7       | Marking of specification control items Marking of commercial off-the-shelf (OTS) items -                            | 7<br><b>7</b> |

#### CONTENTS

| 4.5.8   | Mark     | ing of          | frei           | den         | tif      | ied   | 1 t        | em:             | s -          | -        |     |       | -              |       | _          | _ | _ | - | 7   |
|---------|----------|-----------------|----------------|-------------|----------|-------|------------|-----------------|--------------|----------|-----|-------|----------------|-------|------------|---|---|---|-----|
| 4.5.9   | Meth     | od I (          | type           | ora         | phie     | ral   | ma         | rk ·            | í na         | ì        |     |       | -              | _     | _          | - | _ | _ | 7   |
| 4.5.9.1 | Full     | marki           | ina            |             |          |       | _          |                 |              | <u> </u> | _   |       | _              | _     | _          | _ | _ | _ | 8   |
| 4.5.9.2 | Mini     | เพาก เมา        | rkin           |             |          |       | _          | _ :             |              | _        | _   |       | _              | _     | _          | _ | _ | _ | ĕ   |
| 4.5.10  | Moth     | od II           | lcol           | יש יי<br>חר | rod:     | ina   | ١ .        |                 |              | _        | _   |       | _              | _     | _          | _ | _ | _ | 8   |
| 4.3.10  | rieti    | 100 11          | 1001           | 01          | CUU      | 1 119 | ,          | •               |              | -        | •   |       | •              | -     | •          | • | - | • |     |
| 5.      | DETATI   | . REQUI         | TOCME          | MTC         |          |       |            |                 |              |          |     |       |                |       |            |   |   |   | 10  |
| 5.1     | DETAIL   | . KEQUI         |                |             |          |       | . <b>-</b> |                 |              | _        | - ' |       | -              | -     | -          | - | - | • | 10  |
| 5.2     |          | ical o          |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   |     |
| 5.2.1   | 1 9 0 0  | graphi          |                | mer         | K 1 11 9 | gti   | e c        | not             | 3 1          | ,        | -   |       | -              | -     | -          | • | - | - | 10  |
|         |          | itifyir         |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   | 10  |
| 5.2.2   |          | gn act          |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   | 10  |
| 5.2.3   | "JAN     | l" bran         | <u> 10 (</u> 1 | or          | M11'     | tai   | ry         | \$ P (          | EC 1         | TIC      | at  | 101   | 5 (            | וחכ   | <b>y</b> } |   | - | - | 10  |
| 5.2.4   | Sour     | ce co           | se -           |             |          |       | -          |                 | -            | -        |     | -     | -              | -     | •          | - | - | - | 10  |
| 5.2.5   | Date     | code            |                |             |          |       | -          |                 |              | •        | -   |       | -              | -     | -          | - | - | - | 10  |
| 5.2.6   |          | symbol          |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   | 10  |
| 5.2.7   | Char     | acteri          | istic          | \$ 9        | nd 1     | rati  | Ing        | s ·             |              | -        |     |       | -              | -     | ~          | • | • | - | 11  |
| 5.2.8   | Dist     | ributo          | r's            | \$ y m      | bol      | -     | -          |                 |              | -        |     |       | -              | -     | -          | - | - | - | 11  |
| 5.3     | Colo     | r codi          | ing (          | met         | hod      | 11    | )          |                 |              | -        |     |       | -              | -     | •          | - | - | - | 11  |
| 5.3.1   | Part     |                 |                |             |          |       | -          |                 |              | -        |     | . ~   | -              | -     | ~          | - | - | • | 11  |
| 5.3.2   | Flec     | trical          | cha            | rac         | ter      | ist   | l c s      |                 |              | -        |     |       | _              | -     | -          | _ | _ | _ | 11  |
| 5.3.3   | Othe     | r char          | acte           | ris         | tic      | s a i | nd         | rai             | tin          | q s      |     |       | _              | _     | -          | _ | - | _ | 11  |
| 5.4     | Sens     | itive           | elec           | tro         | nic      | de    | vic        | e (             | (SE          | Ď)       | ite | 2 M S | _              | -     | -          | - | _ | - | 11  |
| 5.5     |          | rity c          |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   | 12  |
| 5.6     | Warr     | anted           | item           | e _         |          |       | _          |                 |              | _        |     |       | _              | _     | _          | _ | _ | _ | 12  |
| J. 0    | Hair     | anced           | 1 6 6 11       | -           | -        |       | -          | - '             | _            |          |     |       |                |       |            |   |   |   | •-  |
| 6.      | NOTES    |                 | _              |             |          |       | _          |                 |              | _        |     |       | _              | _     | _          | _ | _ | _ | 13  |
| 6.1     | 00123    | anency          |                |             |          |       | -          |                 |              | -        |     | _     | -              | -     | _          | - | • | - | 13  |
| 6.2     | rei M    | anency          |                | 20          | 910      |       | ·y         | CE:             | <b>,</b> L 3 | •        | - : |       | •              | -     | -          | - | - | - | 13  |
|         |          | od I m<br>marki | 10 FK 1        | пy          |          | •     | -          |                 | -            | -        |     | •     | -              | -     | -          | - | - | - | 13  |
| 6.2.1   |          |                 |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   |     |
| 6.2.2   |          | lance f         |                |             | -        | -     |            |                 |              |          |     |       | rs             | -     | -          | • | - | - | 14  |
| 6.2.2.1 | Proc     | edures          | for            | n Z         | ing      | the   | t          | a b ]           | es           | t o      | r   | 1     |                |       |            |   |   |   |     |
|         | cyli     | ndrica          | il pa          | rt (        | with     | 1 41  | me         | ns 1            | on           | s o      | 1 ( | . 0   | 91             | 1 11  | Ch         |   |   |   |     |
|         | (2,3     | 11 m111         | imet           | ers         | ) d1     | ame   | ete        | ri              | an d         | 0.       | 25  | 1     | nci            | h     |            |   |   |   |     |
|         |          | 15 m111         |                |             |          |       |            |                 |              |          |     |       |                |       |            |   | - | - | 14  |
| 6.2.2.2 | Proc     | edures          | for            | us          | ing      | the   | t          | a b 1           | es           | fo       | r   | ı f   | 1 a 1          | t     |            |   |   |   |     |
|         | mark     | ing su          | ırfac          | e -         |          | -     | -          |                 | -            | -        |     | -     | -              | -     | -          | - |   |   | 15  |
| 5.3     | EduZ     | ect te          | erm (          | key         | WOT      | rd)   | 11         | sti             | ng           | -        |     |       | _              | -     | _          | - | _ | - | 15  |
| 6.4     | Chan     | ges fr          | on o           | rev         | ious     | s i 9 | SU         | е.              |              | -        |     |       | _              | _     | _          | - | _ | - | 15  |
|         |          | .,              |                | . •         |          |       |            | -               |              |          |     |       |                |       |            |   |   |   |     |
| FIGURES |          |                 |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   |     |
| ,       | A4 . A 4 |                 |                |             |          | 1     |            |                 |              |          |     |       |                |       |            |   |   |   |     |
| 1.      | metn     | od I m          | iarki          | ng (        | e x an   | пріє  | . T        | סר <sub>.</sub> | a p          | pro      | A60 | 1     |                |       |            |   |   |   | _   |
| _       | stan     | dards           | or g           | ove         | rnae     | nt    | SP         | ec 1            | 110          | Cat      | 101 | 15    | . <del>-</del> | -     |            | - | - | - | 7   |
| 2.      |          | 1tive           |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   | 11  |
| 3.      | Exam     | pleof           | War            | ran'        | ty 🛚     | nark  | : in       | 9 -             | -            | -        |     | : :   | -              |       | -          | - | - | - | 12  |
| 4.      |          | od I m          |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   | 13  |
| 5.      | Meth     | od I m          | ıarki          | ng '        | for      | SOL   | ırc        | e c             | on'          | tro      | 1 ( | soc   | u me           | e n t | . \$       | - | - | - | 13  |
| 6.      | Meth     | od I m          | arki           | ng '        | for      | SPE   | 139        | fic             | at           | ion      | C   | nt    | rol            | 1     |            |   |   |   |     |
|         |          | ments           |                |             |          |       |            |                 |              |          |     |       |                |       | -          | - | - | - | 14  |
| TABLES  |          |                 |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   |     |
|         |          |                 |                |             |          |       |            |                 |              |          |     |       |                |       |            |   |   |   |     |
| Ι.      | Orde     | rofp            | rece           | den         | ce f     | or    | ty         | pog             | ra           | ph1      | ca1 | m     | ark            | c 1 n | g          | - | - | - | 8   |
| II.     | Colo     | r code          | s fo           | r p         | art      | 1 de  | nt         | 161             | Ca           | tio      | n r | nar   | kir            | 19    | -          | - | - | - | 9   |
| 111.    | Mini     | mum he          | ight           | re          | quir     | -e d  | fo         | r '             | ' N "        | 11       | ne: | . 0   | ft             | ÿp    | e          | _ | - | - | 16  |
| ΙΥ.     |          | oximat          |                |             |          |       |            |                 |              |          |     |       |                | - '   |            |   |   |   |     |
|         |          | 30 + 0 50       |                |             |          |       |            | •               |              |          |     | _     |                | _     | _          |   |   |   | 1.6 |

#### CONTENTS FSC SECTIONS

| Appendix A | 5905 | Resistors  | 17 |
|------------|------|--|----|
| Appendix B | 5910 |  | 19 |
| Appendix C | 5915 |  | 21 |
| Appendix D | 5920 | Fuses, Fuseholders, Lightning Arresters,   |    |
| Appendix 0 | 3320 | Electrostatic Dischargers, and Telephone Protectors -  | 23 |
| Appendix E | 5925 | Circuit Breakers   | 24 |
| Appendix F | 5930 |  | 26 |
|            | 5935 | Connectors   | 28 |
| Appendix G | 5945 |  | 29 |
| Appendix H |      |  | 33 |
| Appendix I | 5950 |  |    |
| Appendix J | 5955 | Piezoelectric Crystal Units and Ovens  | 36 |
| Appendix K | 5961 |  | 38 |
| Appendix L | 5962 |  | 41 |
| Appendix M | 5985 |  | 43 |
| Appendix N | 5998 | Electrical and Electronic Assemblies, Boards,  |    |
|            |      |  | 44 |
| Appendix O | 5999 | Electrical and Electronic Components, Miscellaneous,   |    |
| • •        |      | Delay Lines  | 46 |
|            |      | • • •  |    |
| FIGURES    |      |  |    |
| 7.         |      | Circuit diagram and terminal identification  |    |
| •          |      |  | 17 |
| 8.         |      | 100 (0505)   | 18 |
| 9A.        |      | Maked to be a second of the se | 22 |
| 9A.<br>9B. |      |  | ۷. |
| 98.        |      | Method I marking example for engineering drawing -   | 22 |
| • •        |      |  | ۷2 |
| 10.        |      | Termination identification for multi-phase   |    |
|            |      |  | 24 |
| 11.        |      |  | 26 |
| 12.        |      |  | 29 |
| 13.        |      | Symbols and markings for relay coil terminals  | 30 |
| 14.        |      | Symbols and color-codes for leadwire terminals   | 32 |
| 15.        |      | Circuit diagram and terminal identification  |    |
|            |      | (FSC 5945)   | 32 |
| 16.        |      |  | 33 |
| 17.        |      | Typical color-coding of cylindrical coils  | 35 |
|            |      |  |    |
| TABLES     |      |  |    |
| ٧.         |      | Characteristic and rating marking requirements   |    |
|            |      | (FSC 5905)   | 18 |
| VI.        |      | Characteristic and rating marking requirements   |    |
|            |      | (FSC 5910)   | 20 |
| VII.       |      | (FSC 5910)   | 30 |
| VIII.      |      | Rating marking requirements  | 34 |

٧

#### 1. SCOPE

- 1.1 Scope. This standard establishes requirements for the physical marking of electrical and electronic parts. This standard should be implemented by incorporating suitable requirements directly in acquisition documents.
- 1.2 Applicability. This standard is intended for FSG 59 and may be applied in acquisition documents to electrical and electronic parts that are covered by other FSG's (such as panel meters, FSC 6625) if desired. The acquiring activity shall evaluate the requirements (sections, paragraphs, or sentences) in this standard to determine the extent to which each requirement can be tailored and be placed on contract in order to impose only the minimum essential needs of the Government. For additional information on application, refer to section 6.
- $1.3\,$  Classification. Marking of parts shall be specified in the acquisition document by the following methods, as applicable.

Method I - Typographical marking Method II - Color coding

#### 2. APPLICABLE DOCUMENTS

#### 2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issue of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

#### STANDARDS

#### MILITARY

MIL-STD-100 MIL-STD-104 MIL-STD-129 MIL-STD-130 MIL-STD-790 MIL-STD-1686 MIL-STD-168

#### **HANDBOOK**

#### MILITARY

DOD-HDBK-263 - Electrostatic Discharge Control Handbook for Protection of Electrical and Electronic Parts, Assemblies and Equipment (Excluding Electrically Initiated Explosive Devices) (Metric).

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issue are those cited in the solicitation.

DOD 4120.3-M - Defense Standardization and Specification Program
Policies, Procedures, and Instructions.
Industrial Security Manual for Safeguarding
Classified Information.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402-0001.)

H4/H8 Section A - Commercial and Government Entity (CAGE) (Name to Code).

H4/H8 Section B - Commercial and Government Entity (CAGE) (Code to Name).

H4/H8 Section C - NATO Supply Code for Manufacturers (Excluding United States and Canada) (Name to Code).

H4/H8 Section D - NATO Supply Code for Manufacturers (Excluding United States and Canada) (Code to Name).

Federal Item Name Directory for Supply Cataloging.

(Application for copies of Cataloging Handbook H4/H8 should be addressed to Commander, Defense Logistics Service Center, ATTN: DLSC-WP, Federal Center, Battlecreek, MI 49017--3084.)

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation.

#### AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C83.1 (EIA-RS-359) - EIA Standard Colors for Color Identification and Coding.

ANSI Y10.19 - Letter Symbols for Units Used in Science and Technology.

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY 10018.)

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 315 - Graphic Symbols for Electrical and Electronic Diagrams.

(Application for copies should be addressed to the Institute of Electrical and Electronics Engineers, 445 Hoes Lane, Piscataway, NJ 08854-4150.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

#### 3. DEFINITIONS

- 3.1 Altered item drawing. When the physical alteration of an existing item, such as that defined by an existing drawing, specification, or standard is required, the required alteration shall be depicted on an altered item drawing.
- 3.2 Commercial and Government Entity (CAGE). The five-position alpha numeric number assigned to manufacturing and nonmanufacturing organizations that design of manufacture-assemble an item of supply acquired and catalogued by DOD agencies (formerly FSCM, see MIL-STD-100).
- 3.3 Commercial item. A term which includes both supplies and parts of a class or kind which is regularly used for other than Government purposes and sold or traded in the course of conducting normal business operations.
- 3.4 Commercial, off-the-shelf (OTS) products (also referred to as commercial products). Products in regular production sold in substantial quantities to the general public or industry at established market or catalog prices.
- 3.5 Design activity. The activity having responsibility for the design of an item. It may be a Government activity, contractor, vendor, or others.
- 3.6 Design activity, current. The activity currently having responsibility for the design, drawing preparation, and maintenance of the design. Current design activity could be the original design activity or a new activity that accepted transfer of responsibility from another Government activity or contractor.
- 3.7 Design activity, identification. The design activity's CAGE (see 3.2) or NSCM (see 3.14).
- 3.8 Design activity, original. The activity that had original responsibility for the design of an item and whose drawing number and CAGE code appear in the title block of the drawing.
- 3.9 Document. The specifications, drawings, lists, standards, pamphlets, reports, or other information (printed or typewritten) relating to the design, acquisition, manufacture, test, or inspection of items under the contract.
- 3.10 Functional marking. The symbols, letters, numbers, and similar marking applied to indicate polarity, circuitry, and similar functional characteristics.
- 3.11 Part or Identifying Number (PIN). The number used to identify an item. It is assigned by the design activity whose engineering drawings, specifications, standards, and inspection requirements control the design of the item. It may be a specification, drawing, part, model, type, catalog, etc., number depending on the numbering system of the design activity.
- 3.12 Manufacturer. A person or firm who owns or leases and operates a factory or establishment that produces (on the premises) materials, supplies, articles, or equipment required under the contract (or for the general character described by the specifications, standards, and publications).
- 3.13 Manufacturer's identification. The actual manufacturer's name, CAGE, or NSCM that identifies the place of manufacture.
- 3.14 NATO supply code for manufacturers (NSCM). The five position alpha numeric code that is assigned to an organization entity, located in the country other than the United States or Canada, that maintains design control or is a source of supply for items acquired by agencies of the Federal Government, NATO member nations, and other participating friendly Governments (see Cataloging Handbook H4/H8).

.....

- 3.15 Order of precedence. The priority for selecting markings when minimum marking is specified.
- 3.16 Part or Identifying Number (PIN) marking. The typographical marking (method I) or color coding (method II) to be applied to the part, tag, label, or unit package to identify the part.
- 3.17 Physical characteristics marking. The symbols, letters, numbers, color codes, and similar markings applied to indicate terminals, leads, and similar physical characteristics.
- 3.18 Acquisition document. The military specification (including specification sheets,  $\frac{1}{2}$  detail specifications, and military sheet form standards), engineering drawing, or specification used for acquisition purposes.
- 3.19 Selected item drawing. Tightened or redefined acceptance criteria, e.g., selection for fit, reliability requirements, or limits within the capability range of existing items such as that depicted on an existing drawing, specification, or standard, shall be delineated on a selected item drawing.
- 3.20 Sensitive electronic devices (SED). Electronic parts having highly sensitive characteristics (e.g., thin-layered internal composition) and delicate, miniaturized construction which are susceptible to damage or degradation, in various degrees, from environmental field forces (electrostatic, electromagnetic, magnetic, or radioactive) as well as more mundane sources such as corrosion, shock, vibration, foreign particle intrusion, biological contamination, thermal stress, and thermal shock. This susceptibility also extends to the standard electronic modules, printed circuit boards, printed wiring boards and circuit card assemblies containing one or more of these sensitive electronic parts.
- 3.21 <u>Sequence of markings</u>. The order for specifying the physical location of markings selected in accordance with the order of precedence.
- 3.22 Source control drawing. A source control drawing depicts an existing commercial or vendor item which exclusively provides the performance, installation, and interchangable characteristics required for one or more specific critical applications.
- 3.23 Special characteristics. The pertinent rating, operating characteristics, and other information necessary for the identification of the item.
- 3.24 <u>Specification control drawing</u>. A specification control drawing depicts an existing <u>commercial item or vendor-developed</u> item advertised or catalogued as available on an unrestricted basis on order as an "off-the-shelf" item or an item while not commercially available, is acquirable on order from a specified segment of an industry.
- 3.25 Specification data. Information such as specification number, type, grade. class, or other identifying data.
- 3.26 Typographical marking. The marking of the part with printed letter and/or number characters.
- 3.27 <u>Warranty</u>. A warranty is the contractual agreement between the Government and the <u>contractor</u> relative to the nature, usefulness, or condition of the item(s) furnished under the contract. Warranty duration is expressed in terms of hours, days, months, number of operations, etc. Warranty markings give notice to a user whether the item(s) is subject to the warrant provisions.

#### 4. GENERAL REQUIREMENTS

- 4.1 General. Functional and part identification marking shall be applied in the location specified in the acquisition document. Where size, surface condition, or other design considerations will not allow marking in accordance with either method I or II, the acquisition document shall specify the method of application (unit package, tay, or label), and the exact marking requirements. Special marking (caution warnings, radioactive) also shall be as specified in the acquisition document. Identification and marking requirements shall be in accordance with sections 4 and 5 of this standard, the applicable FSC section of this standard, and the peculiarities as included in the acquisition document. In the event of conflict between this standard and a acquisition document, the acquisition document shall govern. In the event of conflict between sections 4 and 5 to the requirements of the appendix FSC sections, the FSC sections shall have precedence.
- 4.2 Marking process. Any marking process that will not adversely affect the function of the finished part may be used. Any tags used shall have all burrs and rough edges removed. In addition:
  - a. Marking shall remain legible following completion of all inspections specified in the acquisition document for the normal life expectancy of the part (see 6.1).
  - b. Marking materials shall be nonfading.
  - c. Paper labels for attachment to parts shall not be used.
- 4.3 Symbols. Symbols used in functional and part identification marking shall comform to ANSI Y10.19 or IEEE 315.
- 4.4 Polarity and functional markings. Parts having polarized or other functional characteristics shall always be marked with a polarity symbol or indicators for special flow direction, rotation direction, connections, etc., as specified in the acquisition document. These markings, as applicable, take precedence over all other marking.
- 4.5 Part identification marking. Each part shall be marked in accordance with the full marking or minimum marking requirements stated herein, as specified in the acquisition document. Any other markings that may be applied to the part shall not interfere with, obscure, or confuse those specifications specified herein.
- 4.5.1 Approved standards marking (see MIL-STD-100). An item covered by an approved standard and used without alteration or selection shall be identified by the standard PIN (such as MS number for military specification sheets, see figure 1).
- 4.5.2 Approved government specification marking (see MIL-STD-100). An item covered by an approved government specification containing a part identification system and used without alteration shall be identified by that part identification (see figure 1).
- 4.5.3 Marking parts acquired from, but not manufactured by, the design activity (see MIL-STD-130). When the design activity uses subcontractors for the manufacture of an item, but retains full design control, quality assurance control, and full responsibility to the acquiring activity for the delivered product, only the design activity's CAGE code is required as part of the identifying number. If design control, quality control, or delivered product warranty responsibility is delegated to such subcontractor, then both the design activity's and the subcontractor's CAGE codes are required to be marked on the item.

| Т   |             |                |                                      |
|-----|-------------|----------------|--------------------------------------|
| j   | RER65F1001M | M39XXX/1-1406L | - Identifying number                 |
| 1   | JAN ZZZ     | ) JAN ZZZ      | - "JAN" brand and trademark          |
| ĺ   | 12345 7133A | . 12345 7133A  | - Source code; date code; lot symbol |
| - [ | 1,000ຄ      | 140 μF ±5% 6 V | - Characteristics and ratings        |
| -   | ±1%         | 1              | <b>!</b>                             |
| 1   |             | xxxxxxxx       | - SED symbol if required             |
| 1   |             | 1              | _1                                   |

FIGURE 1. Method I marking example for approved standards or government specifications (see 4.5.1 and 4.5.2).

- 4.5.4 Marking of altered or selected items (see MIL-STD-100). Items which are altered or selected from the controlling specification or standard shall be identified by CAGE code and a part number established by the using design activity drawing which depicts requirements for such alterations or selection.
- 4.5.5 Marking of source control items (see MIL-STD-130). When marking of source control items, they shall be marked with the design activity's CAGE or NSCM code, the source control notation (SOCN), and the source control part number; (example 1234550CN80678932). The vendor's CAGE code and identifying number need not be removed.
- 4.5.6 Marking of specification control items (see MIL-STD-130). When marking specification control items, they shall be marked with the manufacturer's (vendor's) PIN preceded by the manufacturer's CAGE or NSCM code. The specification control drawing number shall not be used to physically reidentify the item from the original design activity's PIN. In the event that a specification control item is a commercial off-the-shelf (OTS) item, refer to 4.5.7.
- 4.5.7 Marking of commercial off-the-shelf (OTS) items (see MIL-STD-130). Commercial OTS items marked with commercial identification (firm name, Togo, PIN, etc.), and which present no identification difficulty may be exempt from additional marking requirements unless otherwise specified by contract or order. This exemption extends to specification control items identified as commercial OTS.
- 4.5.8 Marking of reidentified items (see MIL-STD-100). When items are identified by more than 15 characters (not including the CAGE or NSCM code), or do not meet the other requirements of MIL-STD-100 and a design activity has no control over this assignment, it may assign a design activity control number to the item to meet the identification requirements of that standard.
- 4.5.9 Method I (typographical marking). The applicable markings of table I shall be individually marked on the part or unit package where necessary. Letters shall be without serifs (sans-serifs) such as Gothic of Futura capitals, and the numerals shall be Arabic except when Roman numerals are used for type designation in military specifications and standards. Characters generated by automation techniques (such as interactive graphic systems or stencil) are permitted. Numbers, symbols, trademarks, and other like markings shall be similar in appearance and size to the lettering. When marking processes include the use of marking materials such as inks or paints, these materials shall contrast with the body color of the part to insure legibility. The acquisition document shall specify the sequence and division of line spacing of marking based on the order of precedence specified in table I. However, the sequence may deviate from the order of precedence to accommodate the part configuration and peculiarities of identification marking.

TABLE 1. Order of precedence for typographical markings.

|   | Order of precedence |            |                                   |  |  |  |  |  |  |
|---|---------------------|------------|-----------------------------------|--|--|--|--|--|--|
|   | <br>  Military spe  | cification | <br> <br>  Engineering drawing or |  |  |  |  |  |  |
| Markings $\underline{1}/\underline{2}/$ | Non-ER              | ER 3/      | equipment contractor              |  |  |  |  |  |  |
| SED symbol (see 5.4) 4/                 | 1                   | 1          | 1                                 |  |  |  |  |  |  |
| Identifying number (see 5.2.1)          | 2<br>1              | 2          | 2                                 |  |  |  |  |  |  |
| Design activity code (see 5.2.2         | N/A                 | N/A        | 3                                 |  |  |  |  |  |  |
| "JAN" brand (see 5.2.3)                 | 3                   | 3          | N/A                               |  |  |  |  |  |  |
| Source code (see 5.2.4) 4/              | 4                   | 4          | 4                                 |  |  |  |  |  |  |
| Date code (see 5.2.5)                   | !<br>! 5            | 6          | 5                                 |  |  |  |  |  |  |
| Lot symbol (see 5.2.6)                  | 6                   | 7          | 6                                 |  |  |  |  |  |  |
| Characteristics and ratings (see 5.2.7) | 7                   | 8          | 7                                 |  |  |  |  |  |  |
| Distributor's symbol (see 5.2.8)        | N/A                 | 5          | N/A                               |  |  |  |  |  |  |

- 1/ See 4.4.
- Applicable to tube, semiconductor, microcircuit military specifications and other non-ER military specifications that have provisions for "JAN" brand marking.
- 3/ Refer to MIL-STD-790 for definition on ER and non-ER parts.
- 4/ Applies to devices that are subject to damage or destruction by improper handling or storage.
- 4.5.9.1 full marking. Unless otherwise specified in the acquisition document (see 4.5.9.2), all of the markings listed in table I shall be marked on the part (see 6.2).
- 4.5.9.2 Minimum marking. Where size, surface condition, or other design considerations will not allow full marking on the part (see 6.2.1), the acquisition document shall specify the markings for each part in accordance with the precedence shown in table I.
- 4.5.10 Method II (color coding). When method II is specified in the acquisition document, color codes for part identification shall conform to table II. The standard colors shown in table II shall conform within the preferred limits of the centroid colors specified in ANSI C83.1. The full marking specified in 4.5.9.1 shall be marked on the unit package.

TABLE II. Color codes for part identification marking.

| Color        | Elect                    | rical chara                  | :<br>  Tolerance<br>  value 4th   | !<br>  Failure rate<br>  level symbol |                             |
|--------------|--------------------------|------------------------------|-----------------------------------|---------------------------------------|-----------------------------|
|              | lst code<br>number<br>1/ | 2nd code<br>  number<br>  1/ | 3rd code<br>  multiplier<br>  2/  | code 3/                               | 5th code 4/                 |
| Blk          | o                        | 0                            | 1                                 | ±20% 5/                               | L 6/                        |
| Brn<br>Red   | 2                        | 1 2                          | 10<br>  100                       | ±1%<br>  ±2%                          | M(1%/1000)<br>  P(.1%/1000) |
| 0rn          | 3                        | 3                            | 1,000                             |                                       | R(.01%/1000)                |
| Yel  <br>Grn | <b>4</b> 5               | 4                            | 10,000                            |                                       | s(.001%/1000)               |
| Blu          | 6                        | 5<br>  6                     | 100,000<br>1,000,000              | <br>                                  | <br>                        |
| Yio !        | 7                        | 7                            | 10,000,000                        |                                       |                             |
| Gra (        | 8                        | 8                            |                                   |                                       |                             |
| Wht  <br>Gld | <b>y</b>                 | 9                            | 7/ 0.1                            | <br>  ±5%                             |                             |
| Sil          |                          |                              | 7/       0.1  <br>  7/       0.01 | ±10%                                  |                             |

- $\frac{1}{2}$ / Unless other specified in the acquisition document, the first two code elements shall represent the first and second digits of the electrical characteristic value.
- Except as specified in FSC section 5950, the third code element shall represent the factor by which the two digits are to be multiplied to complete the characteristics value identification.
- $\frac{3}{I}$  . The tolerance value shall be identified by one code element as shown in table II.
- $\frac{4}{}$  The failure rate symbol shall be identified by the last code element. (NOTE: This identification marking shall be applied only when authorized by military specifications.)
- 5/ Body color shall indicate the tolerance for coils.
- 6/ Value as specified in the acquisition document.
- 7/ Not applicable to coils (see FSC section 5950).

#### 5. DETAILED REQUIREMENTS

- 5.1 Physical characteristics marking. Physical characteristics marking shall be as specified in the acquisition document. When color coding is required to identify "numbered" terminals, the colors shall conform to color subcolumn of table II. When the electrical insulation of terminal leads is color coded to identify "numbered" terminals, the colors shall conform to MIL-STD-104.
- 5.2 Typographical marking (method I). When method I marking is specified in the acquisition document, the general and detailed requirements shall be as specified herein.
- 5.2.1 Identifying number. The identifying number shall be as specified in the acquisition document. The identifying number may be a part number as defined in DOD 4120.3-M and MIL-STD-100, a type number (such as 1N2100W or F-1A), or a type designation (such as RNR50C1050FM), or a number identifying a definitive acquisition document which specifies the requirements for the part and the applicable CAGE codes of the manufacturer and design activity. All parts may be marked with a logo, in lieu of the CAGE code, if the product specification or contract so determines they are too small to be marked with a CAGE code.
- 5.2.2 Design activity code. The design activity CAGE code is part of the item identification number and where the manufacturer is not the design activity, both CAGE codes are required on the item except for military specification or approved standards parts (see 6.2) If the CAGE code and the part number are applied on one line, a dash or virgule shall separate the number from the code.
- 5.2.3 "JAN" brand (for military specifications only). The "JAN" brand shall be applied only to parts when authorized by a military specification. For abbreviated marking the "J" may be specified. The "JAN" brand is registered as a U.S. Government certification mark by the U.S. Patent Office (Registration No. 504860).
  - NDTE: The presence of the "JAN" (or "J") brand constitutes certification that the part has met and the manufacturer has not deviated from the specification requirements.
- 5.2.4 Source code. The source code shall identify the manufacturer's plant where the specified quality conformance inspection is performed, or where design and quality assurance responsibility and control is exercised, and shall be the five-digit alpha numeric number assigned in Cataloging Handbook H4/HB.
- 5.2.5 Date code. A four-digit number shall identify the date of the inspection lot and shall be in accordance with the following:
  - Year: The first two digits shall correspond to the last two digits of the calendar year.
  - b. Week: The last two digits shall indicate the week of the calendar year. If only one number is required to indicate the week, it shall be preceded by a zero. The first week shall be considered the week in which the first Thursday of the year falls.
- 5.2.6 Lot symbol. Where a lot symbol is required by the acquisition document, a single letter shall be used to identify a production lot. The letters shall be assigned alphabetically; however, letters "I", "O", "Q", "S", and "U" shall not be used. Where a single letter lot symbols do not cover the number of lots produced, double letters (for example, AA, BB,... AB, AC,... BA, etc.,) shall be used.

- 5.2.7 Characteristics and ratings. Characteristics and ratings shall be as specified in the acquisition document.
- 5.2.8 Distributor's symbol. The distributor's symbol may be marked on the part only when authorized by the manufacturer of the part.
- 5.3 Color coding (method II). When method II marking is applicable, requirements shall be specified in the acquisition document. Color codes for part identification marking shall conform to table II. Requirements shall be coded by using dots or bands as specified in the acquisition document.
- 5.3.1 Part. Certain parts shown in table II shall be identified as such by a single dot or band. This code element, which has no numerical or functional significance, shall be twice the width or diameter of all other code elements and shall simply signify that it is a particular kind of a part. This first code element shall determine from which direction to read the significant code elements. When specified in the acquisition document, the code element also shall indicate polarity or other terminal identification.
- 5.3.2 Electrical characteristics. Functional designations used to denote electrical characteristics, such as resistance, capacitance, inductance, etc., shall conform with table II, unless otherwise specified in the FSC section.
- 5.3.3 Other characteristics and ratings. Other characteristics and ratings shall be as specified in the acquisition document.
  - 5.4 Sensitive electronic device (SED) items.
    - a. Electrical and electronic parts classified as sensitive to damage from electrostatic discharge in accordance with MIL-STD-1686 and DOD-HDBK-263 shall be marked in accordance with the SED symbol (see figure 2).
    - b. Assemblies containing SED parts shall be marked with the SED symbol. This symbol shall be so located as to be readily visible when the assembly is installed in its next higher assembly, if applicable. When the physical size of the assembly precludes direct marking of the SED symbol, the assembly shall be marked on an identification tag and attached securely to the assembly. The SED unit pack shall be marked as specified in MIL-STD-129.



(SYMBOL)

FIGURE 2. Sensitive electronic device (SED) identification.

5.5 Security classification. When required by contract or purchase order, classified items shall be marked in a conspicuous manner to provide notice that the item(s) are subject to security restrictions. Classified marking shall be in accordance with DOD 5220.22-M.

5.6 Warranted items. When specifically required by a contract statement of work or other contract clause, warranted items shall be marked in a conspicuous location to give notice that the item(s) are subject to warranty. The marking shall contain, as a minimum, the statement "WARRANTED ITEM" and the period or conditions of the warranty (i.e., hours of operation, cycles of operation, time since manufactured, etc.) (see figure 3).

| HARRANTED ITEM                     |  |
|------------------------------------|--|
| This item is under warranty until1 |  |

|          | ARRANTED ITEM       |  |
|----------|---------------------|--|
| This ite | m is under warranty |  |

l indicates expiration date.

 $2\,$  indicates condition of use (i.e., hours of operation, time since manufacture).

NOTE: These examples are provided as a guide only and should not be considered mandatory.

FIGURE 3. Example of warranty marking.

#### 6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory)

- 6.1 Permanency and legibility tests. For the purpose of inspecting for permanency and legibility for marking (see 4.2a), the following test methods are recommended for inclusion in the acquisition document:
  - a. Method 215 of MIL-STD-202, "Test Methods for Electronic and Electrical Component Parts."
  - b. Method 2015 of MIL-STD-883, "Test Methods and Procedures for Microelectronics."
  - c. Method 2009 of MIL-STD-883, "Test Methods and Procedures for Microelectronics."

#### 6.2 Method I marking.

6.2.1 Full marking. Figures 1, 4, 5, and 6 show examples of method 1 marking requirements applied in full. These examples are given only as guides and are not to be considered mandatory.

```
68094-XXXXX-X - Design activity CAGE code and Identifying number

ZZZ - Trademark

12345 7133A - Source code; date code; and lot symbol

140 µF ±5% 6 V - Characteristics and ratings

XXXXXXXXX - SED symbol if required
```

FIGURE 4. Method I marking example for commercial parts.

```
| 68094SOCNXXXXXX - Design activity CAGE code and manufacturer's identifying part number | ZZZ - Trademark | 7133A - Date code and lot symbol | 140 uF ±5% 6 V - Characteristics and ratings | XXXXXXXX - SED symbol if required |
```

FIGURE 5. Method I marking for source control documents (see 4.5.5).

12345-80678932 - Manufacturer's CAGE code and manufacturer's identifying part number

- Trademark

7133A - Date code and lot symbol 140 uF #5% 6 V - Characteristics and rating XXXXXXXX - SED symbol if required

FIGURE 6. Method I marking example for specification control documents.

### 6.2.2 <u>Guidance for acquisition document writers</u>. A acquisition document writer can determine how much of the method I marking can be specified as follows:

a. Measure the diameter and the length of the part (using the minimum dimensions) and calculate the circumference to three decimal places (two decimal places if metric units are used) by using the formula:

Circumference = diameter (multiplied by) 3.14 (inches) (inches)

٥r

Circumference = circumference (multiplied by) 25.4 (millimeters) (inches)

- b. Select the size of type and the corresponding number of lines that can be marked within a given marking surface using table III.
- c. Find the number of characters for each line from table IV. (NOTE: A space is to be counted as a character.)
- 6.2.2.1 Procedures for using the tables for a cylindrical part with dimensions of 0.091 inch (2.31 millimeters) diameter and 0.250 inch (5.35 millimeters) lengths.
  - a. Calculate the circumference as:

Circumference =  $0.091 \times 3.14 = 0.285$  inch

or

Circumference = 0.285 x 25.4 = 7.25 millimeters

- b. In table III, find the number equal to or slightly less than .284 (i.e., .284 or .278). Opposite this number at the top of the column is the type size (the type size is 4-point (mini) for .284 and 8-point for .278). In the left-hand vertical column opposite this number, find the number of lines that can be marked on the part. For the 4-point (mini) type, the number is 4; and for the 8-point type, the number is 2.
- c. In the 4-point (mini) type column of table IY, find the specified part length (.250). If this exact number is not in the table, find the next lower number. Opposite this number in the left-hand vertical column is the maximum number of characters that can be marked on each line.
- 6.2.2.2 Procedures for using the tables for a flat marking surface. Where the marking surface is flat, use the procedures of 6.2.2.1b and 6.2.2.1c.
  - 6.3 Subject term (key word) listing.

CAGE code
Characteristic marking
Color codes number
Legibility

Design activity
Functional marking
Identifying number
SED symbol

Lot symbol

6.4 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

TABLE III. Minimum height required for "N" lines of type.

| Number      | j_   | Type size |         |       |     |         |   |                |               |          |  |  |
|-------------|--|-----------|---------|-------|-----|---------|---|----------------|---------------|----------|--|--|
| of<br>lines | 4  | рt        | (mini)  | 4     | рt  | (std)   | 1 | 6 pt           |               | 8 pt     |  |  |
|             | <br>   |           | Mir     | 1 mum | he  | ight (i | 1 | inches) requir | ed <u>1</u> / |          |  |  |
| 1           | <del>                                     </del> | 035       | (0.89)  | 1.0   | 5 6 | (1.42)  | T | .083 (2.11)    | 1 .11         | 1 (2,92) |  |  |
| 2           | 1.   | 118       | (3.00)  | 1.1   | 3 9 | (3.53)  | Ì | .222 (5.64)    | .27           | 8 (7.06) |  |  |
| 3           | 1.   | 210       | (5.33)  | 1 .2  | 22  | (5.64)  | 1 | .361 (9.17)    | 1 .44         | 5 (11.30 |  |  |
| 4           | 1.   | 284       | (7.21)  | 1.3   | 05  | (7.75)  | Ì | .500 (12.70)   | .61           | 2 (15.54 |  |  |
| 5           | 1  | 367       | (9.32)  | 1.3   | 88  | (9.86)  | Ĺ | .639 (16.23)   | 1 .77         | 9 (19.79 |  |  |
| 6           | 1.   | 450       | (11.43) | 1 .4  | 71  | (11.96) | 1 | .778 (19.76)   | .94           | 6 (24.03 |  |  |
| 7           | i.   | 533       | (13.54) | 1 .5  | 54  | (14.07) | i | .917 (23.29)   | [ 1.11        | 3 (28.27 |  |  |
| 8           | i.   | 616       | (15.65) | i .6: | 37  | (16.18) | i | 1.056 (26.82)  | 1 1.28        | 0 (32.51 |  |  |
| 9           | 1.   | 699       | (17.75) | 1 .7  | 20  | (18.29) | Í | 1.195 (30.35)  | 1.44          | 7 (36.75 |  |  |
| 10          | i .  | 782       | (19.86) | 1 .8  | 03  | (20.40) | ì | 1.334 (33.88)  | 1.61          | 4 (41.00 |  |  |

 $<sup>\</sup>frac{1}{}$  Equivalent dimensions in millimeters are shown in the parentheses for general information only.

TABLE IV. Approximate length required for "N" characters of type.

| Number<br>of<br>characters |                  |                  |                  |                 |  |  |  |  |  |
|----------------------------|------------------|------------------|------------------|-----------------|--|--|--|--|--|
|                            | 4 pt (mini)      | l 4 pt (std)     | l 6 pt           | 8 pt            |  |  |  |  |  |
|                            | i<br>  Appro<br> | ximate length (i | n inches) requir | ed <u>1</u> /   |  |  |  |  |  |
| 1                          | .027 (0.69)      | .050 (1.27)      | .070 (1.78)      | .078 (1.98)     |  |  |  |  |  |
| 2                          | .054 (1.37)      | .100 (2.54)      | .140 (3.56)      | 1.156 (3.96)    |  |  |  |  |  |
| 3                          | .081 (2.06)      | 1 .150 (3.81)    | 1 .210 (5.33)    | .234 (5.94)     |  |  |  |  |  |
| 4                          | 1 .108 (2.74)    | 1 .200 (5.08)    | 280 (7.11)       | 1 .312 (7.92)   |  |  |  |  |  |
| 5                          | .135 (3.43)      | 1 .250 (6.35)    | 350 (8.89)       | .390 (9.91)     |  |  |  |  |  |
| 6                          | 1 .162 (4.11)    | 1 .300 (7.62)    | 1 .420 (10.67)   | 468 (11.89)     |  |  |  |  |  |
| 7                          | 1 .189 (4.80)    | .350 (8.89)      | 490 (12.45)      | 1 .546 (13.87)  |  |  |  |  |  |
| 8                          | .216 (5.49)      | 1 .400 (10.16)   | 1 .560 (14.22)   | 1 .624 (15.85)  |  |  |  |  |  |
| 9                          | .243 (6.17)      | 4 .450 (11.43)   | 1 .630 (16.00)   | 1 .702 (17.83)  |  |  |  |  |  |
| 10                         | .270 (6.86)      | 1 .500 (12.70)   | 1 .700 (17.78)   | .780 (19.81)    |  |  |  |  |  |
| 11                         | .297 (7.54)      | 1 .550 (13.97)   | 1 .770 (19.56)   | .858 (21.79)    |  |  |  |  |  |
| 12                         | 324 (8.23)       | 1 .600 (15.24)   | 1 .840 (21.34)   | .936 (23.77)    |  |  |  |  |  |
| 13                         | .351 (8.92)      | 1 .650 (16.51)   | 910 (23.11)      | 1 1.014 (25.76) |  |  |  |  |  |
| 14                         | (9.60)           | 1 .700 (17.78)   | 1 .980 (24.89)   | 1.092 (27.74)   |  |  |  |  |  |
| 15                         | .405 (10.29)     | 1 .750 (19.05)   | 1 1.050 (26.67)  | 1.170 (29.72)   |  |  |  |  |  |
| 16                         | .432 (10.97)     | 1 .800 (20.32)   | 1 1.120 (28.45)  | 1.248 (31.70)   |  |  |  |  |  |
| 17                         | .459 (11.66)     | 1 .850 (21.59)   | 1 1.190 (30.23)  | 1,326 (33.68)   |  |  |  |  |  |
| 18                         | .486 (12.34)     | 1 .900 (22.86)   | 1.280 (32.00)    | 1.404 (35.66)   |  |  |  |  |  |
| 19                         | .513 (13.03)     | 1 ,950 (24,13)   | 1 1.330 (33.78)  | 1 1.482 (37.64) |  |  |  |  |  |
| 20                         | 1 .540 (13.72)   | 1 1.000 (25.40)  | 1 1.400 (35.56)  | 1 1.560 (39.62) |  |  |  |  |  |

 $<sup>\</sup>underline{1}/$  Equivalent dimensions in millimeters are shown in the parentheses for general information only.

<sup>2/</sup> pt = parts in .014 inch (0.35 millimeter) units. Example, 4 pt = .056 inch (1.40 millimeter) letter height.

#### APPENDIX A

#### FSC SECTION 5905 RESISTORS

#### 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking (variable resistors).
- 30.1.1 Terminal identification. Terminals shall be marked so that number 1 represents the counterclockwise terminal, number 2 represents the variable contact terminal, and number 3 represents the clockwise terminal. The terms "counterclockwise" and "clockwise" are used in relation to the actuating device (shaft of screw) when viewed from the exposed operating end.
- 30.1.1.1 Pin or solder-lug type. The numerals designating terminal identification may be marked adjacent to the terminal, or the circuit diagram (see figure 7) may be used, provided that such identification clearly indicates the applicable terminals. The colors, as shown on figure 7, are not required for pin or solder-lug terminal type resistors.
- 30.1.1.2 Flexible-lead type. Colors of flexible-lead insulation shall conform to MIL-STD-104, and terminals shall be identified as follows:

| Terminal number | Color of insulation |
|-----------------|---------------------|
| 1               | Yellow              |
| 2               | Red                 |
| 3               | Green               |

30.1.2 Other functional marking. A circuit diagram shall be marked on any surface of an adjustment type variable resistor (trimmers), in accordance with one of the optional diagrams shown on figure 7.




FIGURE 7. Circuit diagram and terminal identification (FSC 5905).

#### APPENDIX A

#### 30.2 Part identification marking.

- 30.2.1 Marking of resistors. Marking of resistors shall conform to method I or II, as specified in the acquisition document and as shown in table  $\nu$ .
- 30.2.2 Method I. Characteristics and rating shall be marked in the sequence (reading from left to right) of the columnar heading shown under "Order of Precedence" in table Y. Where physical size of the part precludes the marking of all characteristics and ratings, marking requirements shall be specified in the acquisition document in the order of precedence shown by the numerical figures in table Y.

|                                    |   | Order of precedence  |                         |   |   |  |  |  |
|------------------------------------|---|----------------------|-------------------------|---|---|--|--|--|
| Marking method for resistance type |   | <br>  Resistance<br> | Resistance<br>tolerance |   |   |  |  |  |
| Method                             | Resistor type   | <u> </u>             | ,                       |   |   |  |  |  |
| I                                  | <br>  Fixed<br>  {wire-wound)                           | <b>1</b>             | 2                       | 4 | 3 |  |  |  |
| 11                                 | Fixed (composition)                                     | 1<br>1               | 2                       | - | - |  |  |  |
| 1 1/                               | Fixed (film)  | 1                    | 2                       | 4 | 3 |  |  |  |
| 1                                  | Variable<br>  T <b>herma</b> l<br>  th <b>erm</b> istor | 1                    | 2                       | - | 3 |  |  |  |

TABLE V. Characteristic and rating marking requirements (FSC 5905).

- Color-coding may be applicable in acquisition documents approved prior to this standard, and to subsequent revisions of such documents.
- 30.2.3 Method II. Method II marking may be specified in new acquisition documents for composition resistors only. Characteristics shall be marked as shown in table Y by color bands only. (Figure 8 shows the marking of resistors to indicate the resistance value, resistance tolerance, and FR level.) An example for color-coding a 4300 ohms #5 percent, "M" failure rate level composition resistor is:

```
Color-code for first significant figure, yellow (4);
Color-code for second significant figure, orange (3);
Color-code for multiplier, red (times 100);
Color-code for tolerance, gold (45 percent); and
Color-code for faiulre rate level, brown ("M" failure rate level)
```




FIGURE 8. Marking of composition - type resistors.

#### APPENDIX B

#### FSC SECTION 5910

#### 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.
- 30.1.1 Polarity. Polarized capacitors shall be marked as follows:
  - a. A single "+" symbol shall indicate the positive terminal on nontubular and single-ended tubular capacitors.
  - b. A minimum of four "+" symbols shall indicate the positive terminal on axial-lead tubular capacitors. These shall be located approximately 90 degrees apart, at a distance no greater than 25 percent of the total body length away from the positive end of the body and located so as to be readily distinguishable from other markings. Allowance shall be made for proper isolation of the "+" symbols when calculating the maximum number of characters that can be placed on the capacitor.
  - c. All other symbols or markings required shall be as specified in the acquisition document.
- 30.2. Part identification marking.
- 30.2.1 <u>Capacitor marking</u>. Marking of capacitors shall conform to method I or II, as specified in the acquisition document. Characteristics and ratings shall be marked in the sequence (reading from left to right) of the columnar heading shown under "Order of Precedence" in table VI. Other ratings and applicable codes for method II shall be as specified in the acquisition document. Where size characteristics will no accommodate all of these characteristics and ratings, marking shall be as specified in the acquisition document in the order of precedence shown by the numerical figures in table VI.
- 30.2.2 Marking location. All marking of capacitors shall be applied to the body enclosure (excluding any supplementary insulation sleeving). Method II shall be applied starting with (or clockwise from) the "part" code (black).

# MIL-STD-1285B APPENDIX B

TABLE VI. Characteristic and rating marking requirements (FSC 5910).

|                   | Order of precedence |                                     |        |            |         |  |
|-------------------|---------------------|-------------------------------------|--------|------------|---------|--|
| Dielectric        | <br> Capacitance    | <br> Capacitance<br>  tolerance<br> |        | <br>       | Current |  |
| Air:              |                     |                                     |        |            |         |  |
| Fixed             | 1                   | 3                                   | 2      | 4          | -       |  |
| Variable          | 1                   | - 1                                 | 2      | 1 3        | _       |  |
| Ceramic:          | 1                   | 1 .                                 | l<br>: | <b>i</b> : |         |  |
| Fixed             | 1                   | 3                                   | 2      | 4          | -       |  |
| Variable          | 1                   | •                                   | 2      | 3 1        | -       |  |
| Electrolytic:     |                     |                                     |        |            |         |  |
| Fixed             | 1                   | 4                                   | 2      | 3          | -       |  |
| Glass:            | 1                   | 1                                   |        | l i        | ļ       |  |
| Fixed             | 1                   | 3 1                                 | 2      | 4          | -       |  |
| Metallized paper: | 1                   |                                     |        | l i        |         |  |
| Fixed             | 1                   | 3                                   | 2      | 4          | -       |  |
| MICA:             | 1                   | l (                                 |        |            |         |  |
| Fixed             | 1                   | 5                                   | 2      | 4          | 3       |  |
| Paper:            | 1                   | 1                                   |        | ]          |         |  |
| Fixed             | 1                   | l 5 i                               | 2      | 4          | 1/3     |  |
| Paper-plastic:    | 1                   | l l                                 |        | i          | _       |  |
| Fixed             | 1                   | 4                                   | 2      | j 3 l      | -       |  |
| Plastic:          | 1                   |                                     |        |            |         |  |
| Fixed             | 1                   | 1 4 1                               | 2      | ) 3        | -       |  |
| /acuum:           | 1                   | i 1                                 |        | 1          |         |  |
| Fixed             | 1                   | -                                   | 2      | ! 4        | 3       |  |
| Variable          | 1 1                 |                                     | 2      | 1 4        | 3       |  |

<sup>1</sup>/ Applicable to feed-through and by-pass capacitors.

- 1

#### MIL-STD-12858

#### APPENDIX C

#### FSC SECTION 5915 FILTERS AND NETWORKS

#### 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.
- 30.1.1 Terminal identification. Terminals shall be identified as to their function (such as "INPUT", "OUTPUT", "COMMON", "CASE", etc.) using numerals, alphabetic symbols, or their functional names, as specified in the acquisition document. Terminals of radio frequency interference filters need not be identified as to function if the filter is electrically symmetrical. If the filter is not electrically symmetrical, the input or output terminals shall be identified. Broadband electromagnetic interference (EMI) filters which utilize the inductive input, or capacitive input "L" electrical circuit configurations shall be marked such that the symbol "C" (indicating capacitive input), or the symbol "L" indicating inductive input is marked on the filter case at the threaded end of the filter.
- 30.1.2 Other functional marking. Electrical circuit diagrams, cautionary markings, and other markings and symbols shall be as specified in the acquisition document.
  - 30.2 Part identification marking.
- 30.2.1 Filter and radar pulse network marking. Marking of filter and radar pulse forming networks shall conform to method I.
  - 30.2.2 High-pass, low-pass, band-pass, band-suppression, and dual functioning.
- 30.2.2.1 Type marking. Marking shall include the type of filter function (such as high-pass, low-pass, band-pass, band suppression), and the discrimination characteristics referring to the applicable frequencies specified in the acquisition document. Where the lack of space prohibits the inclusion of discrimination characteristics, the design (nominal) center frequency shall be marked on the case for band-pass and band-suppression filters, and the cutoff frequency shall be marked on the case for high-pass and low-pass filters.
- 30.2.2.2 Ratings. Source and load impedance rating shall be marked on the filters in accordance with the requirements specified in the acquisition document. In addition, any other ratings such as dc voltage rating or signal-input voltage rating shall be marked on filters in accordance with the requirements specified in the acquisition document.

#### APPENDIX C

30.2.2.3 Full marking. Figure 9 shows an example of method 1 marking applied in full.

FIGURE 9A. Method I marking example for engineering drawing.

#### 30,2.3 Radio interference.

30.2.3.1 Ratings. Voltage, current and maximum operating (power) frequency ratings, as specified in the acquisition document, and other ratings, specified in the acquisition document shall be marked on the filter.

30.2.3.2 <u>Full marking</u>. Figure 9 shows an example of method I marking applied in full.

FIGURE 9B. Method I marking example for engineering drawing - Continued.

#### 30.2.4 Radar pulse-forming network.

- 30.2.4.1 Characteristics and ratings. Characteristics and ratings shall be as specified in the acquisition document. However, any data or information of a classified nature shall not be marked on the part.
- 30.2.4.2 Contract or purchase order number. The contract or purchase order number shall be marked on each network.
- 30.2.4.3 Serial number. The network's serial number shall be marked on the network.

#### APPENDIX D

## FSC SECTION 5920 FUSES, FUSEHOLDERS, LIGHTNING ARRESTERS, ELECTROSTATIC DISCHARGERS, AND TELEPHONE PROTECTERS

#### 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.
- 30.1.1 Terminal identification. When specified in the acquisition document, lightning arresters, and telephone protectors shall be identified as to their function (such as "LINE", "LOAD", "INSTRUMENT", "INDICATOR", "GROUND", etc.) using numerals, alphabetic symbols, or their functional names as applicable.
- 30.1.2 Other functional marking. Electrical circuit diagrams, cautionary markings, alignment marks, assembly instructions, and other markings and symbols shall be as specified in the acquisition document.
  - 30.2 Part identification marking.
- 30.2.1 Method I marking. Unless otherwise specified in the acquisition document, marking of fuses, fuseholders, lightning arresters, electrostatic dischargers, and telephone protectors shall conform to method I. Where size limitations will not accommodate all of the marking requirements of 5.2, the following requirements and order of precedence shall apply:
  - a. Identifying number.
  - b. Manufacturer's source code, name or trademark.
  - c. Current rating, when applicable.
  - d. Voltage rating, when applicable.
  - e. Date code, when applicable.
  - f. Other ratings and markings, when applicable.
- 30.2.2 Method II color coding (telephone protectors only). The dc breakdown voltage ratings shall be color coded with three dots in accordance with method II, except that the colors to be used shall be as specified in the acquisition document.

#### APPENDIX E

#### FSC SECTION 5925 CIRCUIT BREAKERS

#### 10. SCOPE


10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.

30.1.1 Main terminals. Main terminals shall be marked so that when the circuit breaker is in its normal vertical operating position the main terminals shall be identified with the word "LINE" for the line terminals, and the load terminals shall be identified with the word "LOAD". Where size limitations will not accommodate this marking, the acquisition document shall specify the use of the number "1" to identify the line terminals, and the number "2" to identify the load terminals. For multi-phase circuit breakers, a letter shall be used with the words "LINE" and "LOAD". Where the acquisition document specifies the use of numbers to represent "LINE" and "LOAD", the letters shall precede the number. When viewed from the rear of the circuit breaker, these letters shall be read consecutively from right to left (see figure 10).








FIGURE 10. Termination identification for multi-phase circuit breakers.

- 30.1.2 Auxiliary terminals. Auxiliary terminals shall be identified by lower case letters, consecutively, from right to left or top to bottom as viewed from the rear (see figure 10).
- 30.1.3 Other functional marking. Other functional marking shall be as specified in the acquisition document.

#### APPENDIX E

- 30.2. Part identification marking.
- 30.2.1 Circuit breaker marking. Marking of circuit breakers shall conform to method 1. Additions to the requirements of 5.2 are as follows:
  - a. Eurrent rating.
  - b. Voltage rating.
  - c. Operating frequency, if applicable.
- 30.2.2 Marking location. Unless otherwise specified in the acquisition document, all method I marking except for the main terminal marking, shall be applied to the side of the circuit breaker case. The current rating shall be applied to the exposed end surface of the actuating arm, when specified in the acquisition document.

#### APPENDIX F


#### FSC SECTION 5930 SWITCHES

10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.
- 30.1.1 Polarity (thermostatic switches only). A "+" sign shall be marked adjacent to the positive terminal of a polarized metallic or bimetallic thermostatic switch.
- 30.1.2 Rotary switches. Rotary switch terminals shall be marked with numbers, whose sequence is counterclockwise and visible when viewed from the rear end of the switch, unless otherwise specified in the acquisition document. Open-frame construction switches may be marked with terminal numbers on a marking plate. Dpen-frame construction switches shall be marked with a contrasting color dot, raised or depressed molding, or punched indentation on or near the periphery of the switch section, and marking plate if used. It shall be between terminals 1 and 2 and shall be visible when viewed from the rear end of the switch, unless otherwise specified in the acquisition document.
- 30.1.2.1 Toggle switches. Toggle switch terminals shall be marked in accordance with figure 11 by either raised or depressed numbers. When specified in the acquisition document, the terminal identification may be stamped on the side of the switch case.



NOTE: All views are rear face of switch with lever in the closed (on) position oriented up.

FIGURE 11. Termination identification.

#### MIL-STD-1285B

#### APPENDIX F

30.1.2.2 <u>Snap action and push switches</u>. Terminals of snap action and push switches shall be marked to indicate the contact arrangement as follows (when specified in the acquisition document, the abbreviated marking shall be used):

COMMON or COM, or C NORMALLY OPEN or NO NORMALLY CLOSED or NC

- 30.1.3 Other functional marking. When specified in the acquisition document, a circuit diagram shall be marked on the switch.
  - 30.2 Part identification marking.
- 30.2.1 Switch marking. Marking of switches shall conform to method I. When specified in the acquisition document, additions to the requirements of 5.2 are as follows:
  - a. Current rating.
  - b. Voltage rating.
  - c. Operating frequency, if applicable.

#### APPENDIX G

#### FSC SECTION 5935 CONNECTORS

#### 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.
- 30.1.1 Functional marking. Functional marking shall be as specified in the acquisition document.
  - 30.2 Part identification marking.
  - 30.2.1 Connector marking. Marking of connectors shall conform to method I.
- 30.2.2 Marking location. All marking shall be on the shell of the connector and located in a position to insure readability when the connector is installed in the usual manner.

#### APPENDIX H

#### FSC SECTION 5945 RELAYS

#### 10. SCOPE

 $10.1\,$  Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.

30.1.1 Terminals. Terminals shall be marked in accordance with figure 12. The contact arrangements and symbols are for reference only, and unless otherwise specified in the acquisition document, shall not be marked on the relay. Marking shall be adjacent to the terminals, except where size does not permit such marking, the terminal identification shall be on the circuit diagram only.

|              | S                         | SINGLE THROW                  | DOUBLE THROW       |  |   |
|--------------|---------------------------|-------------------------------|--------------------|--|---|
|              | FORM*A*                   | FORM"B"                       | FORM"C"            | FORM*K* SPOT                                 | FOAM"H"                                     |
|              | NORMALLY OPEN             | NORMALLY CLOSED               | (TWO POSITION)     | 3 POS CENTER OFF                             | 3 POS CENTER O                              |
| SINGLE BHEAK | A1 0 A2  B1 0 B2  C1 0 C2 | A3 0 A2<br>B3 0 B2<br>C3 0 C2 | A1                 | A1 0 A2 A3 0 B1 0 B2 B3 0 B2 C1 0 C2 C3 0 C2 | A1 0 A1 |
| _            | FORM"X"                   | FORM"Y                        | FDAM*Z*            | FORH"KK"                                     | FORM"MH"                                    |
| E BREAK      | A1 0. 1 1. A2             | A30-14 A4                     | A30                | A10 A2<br>A30 1 0 A4                         | 2A 0 1A<br>A3 0 1A                          |
|              | B1 0 # 1 B2               | 83 - B4                       | 830 B4<br>810 4 B2 | B10 B2                                       | 810-082                                     |
| SUUBLE       | cio. de ce                | C30                           | C1 - C2            | C30————————————————————————————————————      | B3 - 64<br>C1 - C2<br>C3 - C4               |

FIGURE 12. Symbols and markings for terminals.

#### APPENDIX H

30.1.1.1 Coil terminals. Coil terminals shall be marked in accordance with figure 13. Unless otherwise specified in the acquisition document, the symbols shown on figure 13 are for reference only and are not intended for marking on the relay.

| SINGLE COIL TERMINALS | DUAL COIL TERMINALS      |
|-----------------------|--------------------------|
| SK W IX BO TX         | TX1 TY2 OR XIMMXZ YIM.YZ |

#### FIGURE 13. Symbols and markings for relay coil terminals.

30.1.1.2 <u>Dual coil terminals</u>. For dual coil relays, the relationship between coil and contacts shall be as specified in table VII.

|                | Contacts closed  |                                 |  |  |
|----------------|--|---------------------------------|--|--|
| Coil energized | Load   | Auxiliary                       |  |  |
| x1-x2          | A1-A2<br>  B1-B2<br>  C1-C1<br>  etc.                            | 11-12<br>31-32<br>51-52<br>etc. |  |  |
| Y1-Y2          | A3-A2 (or A3-A4)<br>B3-B2 (or B3-B4)<br>C3-C2 (or C3-C4)<br>etc. | 21-22<br>41-42<br>61-62<br>etc. |  |  |

TABLE VII. Dual coil relay markings.

- 30.1.1.3 Leadwire insulation marking. Leadwire terminals shall be color-coded on the insulators in accordance with figure 14 and MIL-STD-104. Figure 14 shows the color-codes associated with the terminal numbers. The contact arrangements and symbols are for reference only, and, unless otherwise specified in the acquisition document, shall not be marked on the relay.
- 30.1.1.4 Polarity marking. Terminal X1 shall be marked with a plus (+) sign for polarized relays. When specified in a acquisition document, this terminal shall be identified by a blue-colored bead.
- 30.1.2 Other functional marking. Where applicable, the acquisition document shall specify the direction of maximum sensitivity to shock, vibration, acceleration and similar characteristics. Unless otherwise specified, a circuit diagram shall be marked on one of the surfaces vertical to the terminal surface. Figure 15 shows an example of a typical circuit diagram marking.

# APPENDIX H

- 30.2 Part identification marking.
- 30.2.1 Relay marking. Marking of relays shall conform to method I. Characteristics and ratings shall be marked in the following order of precedence:
  - a. Rated coil voltage (or current).
  - b. Operating frequency (if applicable).
  - c. Contact ratings.

Where size limitations will not accommodate these characteristics and ratings, marking requirements shall be specified in the acquisition document in the order of precedence shown above.

30.2.2 Marking location. Unless otherwise specified in the acquisition document, all method I marking shall be applied to the top surface (opposite the terminal surface) of the relay case.

# APPENDIX H




FIGURE 14. Symbols and color codes for leadwire terminals.




FIGURE 15. Circuit diagram and terminal identification (FSC 5945).

### MIL-STD-12858

### APPENDIX 1

# FSC SECTION 5950 COILS, INDUCTORS, AND TRANSFORMERS

# 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.
- 30.1.1 Terminal identification. The terminals shall be identified by numbers or color-coding, as specified in the acquisition document. Insulated terminals shall conform to MIL-STD-104. Where numbering or color-coding of terminals is not practical, the acquisition document shall specify the alternate terminal identification.
- 30.1.2 Other functional marking. A circuit diagram shall be marked on the side or top of the transformer or inductor as shown on figure 16. Unless otherwise specified in the acquisition document, the ratings that are to be marked on the circuit diagram shall be as shown in table VIII. Where size limitations will not accommodate all of these ratings, marking requirements shall be specified in the acquisition document in the order of precedence shown in table VIII.




FIGURE 16. Examples of typical circuit diagrams.


# APPENDIX I

TABLE VIII. Rating marking requirements.


| Part   | Primary  | Secondary                          |
|--|--|------------------------------------|
| Power, vibrator,<br>inverter, and line<br>input transformers               | Rated voltage, frequency, and working voltage.   | Rated voltage(s) and current(s)    |
| Inductors  | Rated inductance, voltage, dc current, dc resistance, frequency and working voltage.                         | Not applicable                     |
| Single-frequency audio inductors or transformers (except audio oscillator) | Source impedance, dc current, frequency range, power level in watts, and working voltage.                    | Load impedance and working voltage |
| Audio oscillator<br>transformer  | DC current, frequency range, power level, and working voltage.   | DC current                         |
| Pulse transformers<br>(except pulse<br>oscillator)                         | Pulse width and duty cycle, pulse, polarity, source impedance, operating voltage, and current.               | Load impedance and current         |
| Pulse oscillator<br>transformer  | DC resistance, turns ratio, operating voltage and current, repetition rate, duty cycle, and working voltage. | Not applicable                     |
| Saturable-core inductor and transformer                                    | Maximum control current, impedance, impedance variation, rated voltages, frequency, and working voltage.     | Not applicable                     |

- 30.2 Part identification marking.
- 30.2.1 Transformer marking. Marking of transformers shall conform to method I.
- 30,2.2 Coils marking. Marking on coils shall conform to method I or II.
- 30.2.2.1 Cylindrical coils marking. Cylindrical coils shall conform to method II except when the inductance value is less than 10 microhenries, the first or second code shall be gold to represent the decimal point; the other two codes will represent the characteristic values. (Figure 17 shows the marking to indicate military part identifier, inductance value, and inductance tolerance.)

# MIL-STD-1285B APPENDIX I



Typical color coding under 10 microhenries



Typical color coding

FIGURE 17. Typical color coding of cylindrical coils.

#### APPENDIX J

# FSC SECTION 5955 PIEZOELECTRIC CRYSTAL UNITS AND OVENS

### 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

# 20. APPLICABLE DOCUMENTS

# 20.1 Government documents.

20.1.1 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

NAVSHIP 0967-LP-190-4010 - Manufacturer's Designating Symbols.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

# 30. GENERAL REQUIREMENTS

# 30.1 Functional marking.

30.1.1 Crystal oven terminals marking (octal base). Pin-type terminals shall be marked so that when an octal-base crystal oven is viewed from the bottom, number 1 will be adjacent to and clockwise from the socket key. All other terminals shall be identified clockwise from this pin. Insulated, flexible leads shall be color-coded in accordance with MIL-STD-104.

# 30.2 Part identification marking.

30.2.1 Oscillators and crystal units. The frequency shall be specified to the final Hertz and shall be identified by a fixed field of eight characters consisting of seven digits and a letter (H, K, or M) representing simultaneously, the decimal point and the appropriate multiplier as follows:

- a. Less than 1 Hertz and less than 1,000 Hertz, the letter "H" is used to represent the decimal point and multiplier.
- b. Greater than or equal to 1,000 Hertz, but less than 1 Megahertz, the letter "K" is used to represent the decimal point and multiplier.
- c. Greater than or equal to 1 Megahertz, the letter "M" is used to represent the decimal point and multiplier.

All digits preceding and following the letter (H, K, and M) of the group represent significant figures.

# APPENDIX J

The following are examples of using the eight characters in constructing the specified frequency.

# Designation

# Frequency

| H0100000 to<br>1H000000 to<br>10H00000 to<br>100H0000 to<br>1K000000 to<br>10K00000 to<br>1M000000 to<br>10M00000 to | 9H999999<br>99H99999<br>999H9999<br>9K999999<br>99K99999<br>9M999999 | .01 to .9999999 Hertz, inclusive 1.0 to 9.999999 Hertz, inclusive 10 to 99.99999 Hertz, inclusive 100 to 999.9999 Hertz, inclusive 1 to 9.99999 kilohertz, inclusive 10 to 99.99999 kilohertz, inclusive 100 to 999.9999 kilohertz, inclusive 1 to 9.99999 megahertz, inclusive 10 to 99.99999 megahertz, inclusive 10 to 99.99999 megahertz, inclusive 100 to 999.99999 megahertz, inclusive 100 to 999.99999 megahertz, inclusive |
|--|--|---|
| TOOMODOD to  | 999M9999   | 100 to 999.9999 megahertz, inclusive  |

# 30.2.2 Marking location.

- 30.2.2.1 <u>Crystal units marking</u>. The identifying number, frequency, and source code shall be located symmetrically with respect to the center axis of the crystal holder.
- 30.2.2.2 Crystal ovens marking. Part identification shall be marked on the side of the case.

### APPENDIX K

# FSC SECTION 5961 SEMICONDUCTOR DEVICES

# 10. SCOPE

1

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

# 20. APPLICABLE DOCUMENTS

# 20.1 Government documents.

20.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

### SPECIFICATION

MILITARY

MIL-S-19500 - Semiconductor Devices, General Specification for.

# STANDARD

MILITARY

MIL-STD-750 - Test Methods for Semiconductor Devices.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099).

20.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

NAVSHIP 0967-LP-190-4010 - Manufacturer's Designating Symbols.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

### MIL-STD-12858

#### APPENDIX K

- 30. GENERAL REQUIREMENTS
- 30.1 Military specification devices.
- 30.1.1 Devices covered by MIL-S-19500. Marking of semiconductor devices covered by MIL-S-19500 and its associated detail specifications shall conform to method I and the following:
  - a. Polarity marking (diodes and thyristors only).
  - b. Type designation, including "JAN" or "JANTX" prefix as applicable (see 30.1.6).
  - c. Inspection lot identification code (see 30.1.7).
  - d. Manufacturer's designating symbol (see 30.1.8).
  - e. Manufacturer's identification (see 30.1.9).
  - f. Country of origin (see 30.1.10).
- 30.1.2 Unit pack marking. All of the marking specified in all the above, except polarity, shall appear on the carton, box, plastic envelope, and so forth, used as the initial protection or wrapping for delivery. Marking shall be in conformance with MIL-STD-129. Duplicate information need not be repeated.
- 30.1.3 Special marking. If any special marking is used, it shall in no way interfere with or obscure the marking required in all the above and shall be completely separated therefrom.
- 30.1.4 Permanence of marking. Permanence of marking shall be in accordance with MIL-STD-750, method 1022.
- 30.1.5 Diodes and unidirectional thyristors polarity marking. The polarity shall be indicated by one of the following methods.
- 30.1.5.1 Diodes. Polarity marking shall be by either an arrow or diode graphic symbol with the arrow pointing towards the negative terminal for forward bias or by a single contrasting color band or dot adjacent to the cathode terminal for forward bias.
- 30.1.5.2 Thyristors. A graphic symbol for a thyristor with the arrow pointing towards the  $\overline{\text{cathode terminal}}$ .
- 30.1.6 "JAN", "JANTX", "JANTXY", or "JANS" prefix. The type designation shall bear the prefix "JAN", "JANTX", "JANTXY", or "JANS", as applicable, except that for small devices, the prefix "J", "JX", "JY", or "JS", may be used.
- 30.1.7 Inspection lot date code. Semiconductor devices shall be marked by a code indicating the date the lot was submitted for inspection. The first two numbers in the code shall be the last two digits of the number of the year. The third and fourth numbers shall be two digits indicating the calendar week of the year. When the number of the week is a single digit, it shall be preceded by a zero. Reading from left to right or from top to bottom, the code number shall designate the year and the week, in that order. When more than one lot of a type is inspected for conformance within the same week, and inspection lot suffix letter shall be chosen, consisting of a single capitol letter, and shall appear on each semiconductor device immediately following the submission date. This letter shall be chosen by the manufacturer so that each inspection lot is uniquely identified by the submission date and by the lot-identification suffix letter, if one is required.

#### APPENDIX K

- 30.1.8 Manufacturer's designating symbol. The manufacturer's designating symbol shall be as listed in NAVSHIPS 0967-LP-190~4010. The designating symbol shall be used only by the manufacturer to whom it has been assigned and only on those devices manufactured at that manufacturer's plant. In the case of small devices, the manufacturer's designating symbol may be abbreviated by omitting the first "C" in the series of letters.
- 30.1.9 Manufacturer's identification. Semiconductor devices shall be marked with the name or trademark of the manufacturer who has contracted to manufacture devices for the Government or its equipment manufacturers, and at whose plant the specified quality conformance inspection has been performed. The identification of the equipment manufacturer may appear on the device only if the equipment manufacturer is also the device manufacturer. The name or trademark of only the original manufacturer shall appear on the device or initial container. Rebranding shall not be permitted.
- 30.1.10 Country of origin. The phrase "Made in U.S.A." shall be marked in small characters below or adjacent to other marking specified in paragraph 1 except that, for semiconductor devices made in a foreign country, the phrase shall be changed accordingly.
- 30.1.11 Marking option. The manufacturer has the option of marking the entire lot or only the sample devices to be subjected to quality conformance inspection. If the manufacturer exercises the option to mark only the sample devices, the procedure shall be as follows:
  - a. The sample devices shall be marked prior to performance of quality conformance inspection.
  - b. At the completion of inspection, the marking of the sample devices shall be inspected for conformance to the requirements of this standard.
  - c. The inspection lot represented by a conforming inspection sample shall then be marked and any specified visual and mechanical inspection performed.
  - d. The marking materials and processing applied to the inspection lot shall be the same specifications as those used for the inspection sample.
  - 30.2 Non-military specification devices.
- 30.2.1 Marking of devices other than MIL-S-19500. Marking of semiconductor devices covered by acquisition documents other than MIL-S-19500 shall conform to method I and the following order of precedence (see table I):
  - a. Polarity marking (diodes and thyristors only, see 30.1.5 of this appendix).
  - b. Identifying number (see 5.2.1).
  - c. Design activity code (see 5.2.2).
  - d. Source code (see 30.1.8 of this appendix).
  - e. Bate code and lot symbol (see 30.1.7 of this appendix).
  - f. Manufacturer's identification (see 30.1.9 of this appendix and note 2 of table 1).
  - g. Country of origin (see 30.1.10 of this appendix).

The second secon

# MIL-STD-1285B

#### APPENDIX L

# FSC SECTION 5962 MICROELECTRONIC CIRCUIT DEVICES

### 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

# 20. APPLICABLE DOCUMENTS

# 20.1 Government documents.

1

20.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

### SPECIFICATIONS

### MILITARY

MIL-M-38510 - Microcircuits, General Specification for.
MIL-H-38534 - Hybrid Microcircuits, General Specification for.
MIL-I-38535 - Integrated Circuits (Microcircuits), Manufacturing,
General Specification for.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

# 30. GENERAL REQUIREMENTS

# 30.1 Military specification devices.

- 30.1.1 <u>Marking</u>. For marking requirements of microelectronic circuit devices covered by MIL-M-38510, MIL-H-38534, and MIL-I-38535, and the associated detail specifications, see the applicable general specification (i.e., MIL-M-38510, MIL-H-38534, or MIL-I-38535).
- 30.1.2 Marking of Standardized Military Drawings (SMD's). For marking requirements of microelectronic circuit devices covered by SMD's, see the applicable drawing. If any special marking (e.g., altered item drawing number) is used by the device supplier or user/equipment contractor, it shall be in addition to the existing/original marking as required in the applicable detail drawing and shall be visibly separate from and in no way interfere with the marking required by the SMD.

# 30.2 Permanency and legibility.

30.2.: Permanence and legibility of marking. The marking shall be permanent, legible and shall meet the marking permanence requirements of the applicable general specification (i.e., MIL-M-38510, MIL-H-38534, or MIL-I-38535).

#### APPENDIX L

# 30.3 Non-military (e.g., SCD, SID, and AID) specification devices.

- 30.3.1 Acquisition documents other than military specification devices. Marking of microelectronic circuit devices covered by acquisition documents other than MIL-M-38510. MIL-H-38534, and MIL-I-38535 and SMD's shall conform to method I and the following order of precedence.
  - a. Index point (for example, see MIL-M-38510).
  - b. Part or Identifying Number (PIN) (see 5.2.1).
  - c. Design activity code (see 5.2.2).
  - d. Source code (see 5.2.4).
  - e. Inspection lot identification code (for example, see MIL-M-38510).
  - f. Lot symbol (see 5.2.6).
  - g. Serialization, when applicable (for example, see MIL-M-38510).
  - h. Manufacturer's identification (for example, see MIL-M-38510).
  - i. Country of origin.
  - Electrostatic discharge sensitivity identifier (for example, see MIL-M-38510).
- 30.3.2 Marking of altered or selected items (see MIL-STD-100). Items which are altered or selected from the controlling specification or standard shall be identified by a part number established by the using design activity drawing which depicts requirements for such alterations or selection. The original number being replaced shall not be removed or obliterated.

# 30.4 Functional marking.

- 30.4.1 <u>Terminal index feature</u>. An index feature shall be visible from the top or bottom of microelectronic circuit packages and located near the package periphery.
- 30.4.1.1 Peripheral lead packages. For the peripheral lead packages (flat pack and dual-in-line), convention shall be that when viewed from the top, terminal number 1 shall be adjacent to or immediately counterclockwise from the index feature. Other terminal positions shall then be successively numbered counterclockwise from terminal 1.
- 30.4.1.2 Axial lead packages. For axial lead packages, convention shall be that when viewed from the bottom, terminal 1 shall be the next terminal position clockwise from the terminal index feature.

# 30.5 Identification marking location.

30.5.1 Marking location and sequence. The part number, identification codes and ESDS identifier shall be located on the top surface of leadless or leaded chip carrier packages, pin grid array packages, flat packages, or dual-in-line configurations and on either the top or the side of cylindrical packages (TO configurations and similar configurations). When the size of a package is insufficient to allow marking of special process identifiers on the top surface, the backside of the package may be used for these markings except the ESDS identifier shall be marked on the top. Button cap flat packs with less than or equal to 16 leads may have the identifier marked on the ceramic. Backside marking with conductive or resistive ink shall be prohibited.

# APPENDIX M

# FSC SECTION 5985 ANTENNAS, WAVEGUIDES, AND RELATED EQUIPMENT

- 10. SCOPE
- 10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Functional marking.
- 30.1.1 Functional marking. No markings are defined.
- 30.2 Part identification marking.
- 30.2.1 Antennas, waveguides, and related equipment. Marking of antennas, waveguides, and related equipment shall conform to method I. Exceptions or additions to the requirements of section 5.2 shall be as specified in the acquisition document.

1

# MIL-STD-12858

# APPENDIX N

FSC SECTION 5998 ELECTRICAL AND ELECTRONIC ASSEMBLIES, BOARDS, CARDS, AND ASSOCIATED HARDWARE PRINTED WIRING BOARDS.

10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS
- 20.1 Government documents.
- 20.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

SPECIFICATION

MILITARY

MIL-P-55110 - Printed Wiring Boards.


(Unless otherwise inuicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

- 30. GENERAL REQUIREMENTS
- 30.1 Part identification marking.
- 30.1.1 Guides and extractors/ejectors marking. Card guides and card extractors/ejectors do not require marking of parts.

### APPENDIX N

30.1.2 Method I marking. Unless otherwise specified in the acquisition document, marking of printed wiring boards shall comform to method I.

Each individual board, each qualification board, and each set of quality conformance test circuits strips (as opposed to each individual coupon) shall be marked in accordance with the master drawing, with the date and the manufacturer's CAGE code. All markings shall be compatible with materials and parts, legible after all tests, and in no case affect the board performance. Marking shall be tested in accordance with MIL-P-55110. In addition to this marking, the use of bar code marking is permissible. Coupon marking shall be representative of the board marking. The date code shall be formatted as follows:



This date shall reflect the first copper plating.

### APPENDIX O

# FSC SECTION 5999 ELECTRICAL AND ELECTRONIC COMPONENTS, MISCELLANEOUS DELAY LINES

# 10. SCOPE

10.1 Scope. The following define the requirements that pertain to both commercial and military electronic devices. Where the requirements are not stated, refer to sections 4 and 5 herein. This appendix is a mandatory part of this standard. The information contained herein is intended for compliance.

This appendix establishes the marking requirements that apply to a specific federal stock class (FSC). These requirements are to be applied in addition to the requirements of sections 4 and 5 herein. In the event of conflict between this appendix and section 4 or 5, the appendix shall take precedence.

- 20. APPLICABLE DOCUMENTS. This section is not applicable to this appendix.
- 30. GENERAL REQUIREMENTS
- 30.1 Parts identification marking.
- 30.1.1 Mounting pads, gaskets, and heat sinks marking. Mounting pads, gaskets, and heat sinks do not require marking of parts.
- 30.1.2 Method I marking. Unless otherwise specified in the acquisition document, marking of delay lines shall conform to method I.
  - a. "JAN" or "J" marking.
  - b. Military part number.
  - c. Index mark identification (next to pin 1, input).
  - d. Manufacturer's source code or logo.
  - e. Date code.

# CONCLUDING MATERIAL

Custodians:
Army - ER
Navy - EC
Air Force - 85
DLA - DH

Review activities:
Army - AR, ME, MI
Navy - AS, EC, MC, OS, SH, YD
Air Force - 11, 17, 99
DLA - ES

Preparing activity:
Army - ER

Agent:
DLA - ES

(Project 59GP~0077)

# STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

# INSTRUCTIONS

- 1. The preparing activity must complete blocks 1, 2, 3, and 8 in block 1, both the document number and revision letter should be given.
- 2. The submitter of this form must complete blocks 4, 5, 6, and 7.
- The preparing activity must provide a reply within 30 days from receipt of the form.

| 3. The preparing activity must prov                                  | •                                    | •  |          |
|--|--------------------------------------|--|----------|
| requirements on current contracts.                                   | Comments submitted on this f         | ints, nor to request waivers, or clarification form do not constitute or imply authorization | of<br>to |
| waive any portion of the referenced                                  | document(s) or to amend cont         | ractual requirements.  |          |
| I RECOMMEND A CHANGE:  | 1. DOCUMENT NUMBER                   | 2. DOCUMENT DATE (YYMMDD)  |          |
|  | MIL-STD-1285B                        | 15 February 1990   |          |
| 3. DOCUMENT TITLE  |                                      | - · · · · · · · · · · · · · · · · · · ·  |          |
| MILITARY STANDARD Marking 4. NATURE OF CHANGE (Identify paragraph of | of Electrical and Elect              | ronic Parts  |          |
| . NATONE OF CHANGE (Wentily paragraph in                             | iumber and include proposed rewrite, | ir possible. Attach extra sneets as needed.)   |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
| PEACON COO DECOMMENDATION  |                                      |  |          |
| . REASON FOR RECOMMENDATION  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  |          |
|  |                                      |  | _        |
| SUBMITTER  |                                      |  |          |
| ı. NAME (Ləx, Firx, Middle India)                                    | b. ORGANIZ                           | LATION   |          |
| . ADDRESS (Include Zip Code)   | d. TELEPHO                           | HE (Include Ares Code) 7. DATE SUBMITTED   |          |
|  | (1) Commen                           | (COMMOO)   |          |
|  | (Z) AUTOVO                           |  |          |
|  | (If applic                           | <b>&gt;b(4)</b>  |          |
| PREPARING ACTIVITY   |                                      |  |          |

| a. NAME (Loss, First, bricklin halling) | b. ORGANIZATION  |                               |
|---|--|-------------------------------|
| c. ADDRESS (include Zig Code)           | d. TELEPHONE (include Ares Code) (1) Commercial (2) AUTOVON (If applicable)  | 7. DATE SUBMITTED<br>(YYMMOO) |
| 8. PREPARING ACTIVITY                   |  |                               |
| a. NAME                                 | b TELEPHONE (Include Area Code) (1) Commercial   | (2) AUTOVON                   |
| US Army Laboratory Command              | (201)544-3441  | 995-3441                      |
|   | IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466  O() Telephone (703) 756-2340 AUTOVON 289-2340 |                               |