


FED. SUP CLASS
4130

PART NO.	CAPACITY LBS. AIR/MIN (MIN)	RELIEF SETTING (P.S.I.G.)	CONNECTION SIZE (INCHES)	
			NPTF	FLARE
MS17415-1	3.2	300	3/8	3/8

NOTES

- For use with dichlorodifluoromethane (CCl_2F_2) R-12, Refrigerant.
- ALL CONNECTIONS SHALL BE MALE. FLARE CONNECTION SHALL CONFORM TO MS 35873. NPTF CONNECTION SHALL CONFORM TO MS 35368.
- VALVE SHALL BE SPRING LOADED, ANGLE TYPE BODY, CONFIGURATION 1 OR 2.
- ALL DIMENSIONS ARE IN INCHES.
- REFERENCED DOCUMENTS SHALL BE OF THE ISSUE IN EFFECT ON DATE OF INVITATION FOR BID OR REQUEST FOR PROPOSAL.
- FOR DESIGN FEATURE PURPOSES, THIS STANDARD TAKES PRECEDENCE OVER PROCUREMENT DOCUMENTS REFERENCED HEREIN.

APPROVED 2 JAN 62 REVISED (A) 24 NOV 65 (B) 1 FEB 71

This Military standard is mandatory for use by all Department and Agencies of the Department of Defense. Selection for all new engineering and design applications and for repetitive use shall be made from this document.

User
Army - CE
Navy - MC

Review
Army - ME

P.A. ARMY GL Other Cust	TITLE VALVE, SAFETY RELIEF, REFRIGERANT-12	MILITARY STANDARD
NAVY - YD		MS 17415
PROCUREMENT SPECIFICATION MIL-V-23/35	SUPERSEDES:	SHEET OF

DD FORM 672-1 (Coordinated)

PREVIOUS EDITIONS OF THIS FORM ARE OBSOLETE.